

426 Industrial Avenue, Suite 164 • Williston, VT 05495 Phone: (802) 862-9381

www.mjinc.com

April 29, 2022

MJ Project No. 18438.09

Mr. Rob Hepburn State of Vermont Department of Buildings and General Services 133 State Street, 5th Floor Montpelier, VT 05633

Re: Southeast State Correctional Facility Conceptual Master Plan and Cost Estimates Town of Windsor, Vermont

Dear Mr. Hepburn:

The goal of this report is to provide the State of Vermont Department of Buildings and General Services (VT BGS) with information and budgetary cost information to assist in their evaluation of four (4) options regarding the future of the ± 118 -acre, Southeast State Correctional Facility Campus in the Town of Windsor, Vermont.

The overall scope of the project consisted of the following: a facility walkthrough of the existing campus conducted by Mark Blanchard of VIS Construction Consultants (VISCC) on April 14, 2022 to document site and building conditions; reviewing existing pertinent data, reports, and site/utility drawings to help develop a conceptual master plan for each option; evaluation of each option for either renovation or demolition of all structures, infrastructure, and utilities or portions thereof, and how their removal will impact adjacent utilities or buildings; preparation of a brief narrative describing each option including an opinion of probable cost estimates; and identification of potential permits required to accomplish the work for each option, all as further described below:

OPTION A

Option A includes demolition of thirty-one (31) buildings (includes 3 water supply/pump/storage structures); utilities; eight (8) fuel storage tanks (5-above ground and 3-underground); asphalt areas; perimeter/interior fencing, posts, and foundations; and restoring the site/disturbed areas with vegetation. A Site Demolition Plan for Option A is provided as drawing S-1 in Appendix A.

Portions of the existing asphalt and gravel roadways will remain to provide access to the site and thru traffic from State Farm Road to Marton Road. Utilities will be removed back to the nearest main, pole, and/or structure. The majority of the existing overhead primary electric; storm sewer; and 8" sanitary trunk sewer systems will remain to provide primary services for potential future development. A Site Plan showing the exiting features/utilities to remain for Option A is provided as drawing S-2 in Appendix A.

The total project cost for Option A is estimated to be \$5,463,000.00, an itemized breakdown of the opinion of probable cost estimate is provided in Appendix B.

Required Permits:

- Vermont Department of Environmental Conservation Act 250 (Average processing time: 60 to 80 days).
- Construction Stormwater Discharge Permit Vermont's Construction General Permit (CGP) (Average processing time: 40 to 60 days)
- Notification to the Underground Storage Tank Program for removal of underground storage tanks.
- Local and/or State Approvals and Building/Demolition Permits.

OPTION B

Option B includes partial demolition of utilities and buildings that do not provide value or need a considerable amount of renovation to make useable. Based on the facility walkthrough and consultation with VT BGS staff it was determined that five (5) buildings be deemed useable for this option as further discussed below:

- 1. Education Building (#04) Heat to this building is currently fed from the existing boiler house to be demolished; a new propane boiler/HVAC system will need to be installed to make the building useable.
- 2. North Country Dormitory Building (#07) This building has its own boiler/HVAC system and is considered useable in its current state; however, it is recommended that the existing fuel oil tank be removed, and the existing boiler system be converted to propane fuel.
- 3. Administration Building (#08) Heat to this building is currently fed from the existing boiler house to be demolished; a new propane boiler/HVAC system will need to be installed to make the building useable.
- 4. Plate Shop/Workshop Building (#09) Heat to this building is currently fed from the existing boiler house to be demolished; a new propane boiler/HVAC system will need to be installed to make the building useable.
- 5. Sign/Machine Shop Building (#10) This building is considered useable for cold storage only as it is not currently heated or connected to water or sanitary sewer systems.

There was also discussion regarding other buildings that were thought to be useable but were deemed to be not useable as further discussed below:

- 1. BGS Maintenance Office (#015) This is one of the original buildings on-site and would require considerable renovation work on the interior of the building to make it useable as well as to meet ADA accessibility requirements for any other use than residential.
- 2. BGS Garage (#02) Could be a storage/maintenance building, however, it needs a new a roof to make it useable which will be more than the cost of demolition.
- 3. Dorm & Dining Building (#05) Structurally the building is sound and appears in good condition on the outside, however, it would take considerable renovation work on the interior of the building to make it useable as well as to meet ADA accessibility requirements.

Based on the above discussions Option B will include demolition of twenty-four (24) buildings, utilities, eight (8) fuel storage tanks (5-above ground and 3-underground); asphalt areas; perimeter/interior fencing, posts, and foundations; and restoring the site/disturbed areas with vegetation. A Site Demolition Plan for Option B is provided as drawing S-3 in Appendix A.

Portions of the existing asphalt and gravel roadways will remain to provide access to the useable buildings, site, and thru traffic to State Farm Road. Utilities from demolished buildings will be removed back to the nearest main, pole, structure, and/or building. To provide services to the useable buildings a majority of the existing overhead primary electric; storm sewer; sanitary sewer; and domestic and fire water systems will need to remain including the Fire Pump House (#26) and Water Supply/Storage (#29). The heating/boiler, domestic water, telephone, and fiber optic utility systems for the Education Building (#04), Administration Building (#08), and Plate Shop/Workshop Building (#09) to remain are currently supplied from the Dorm Dining (#05) building to be demolished which will require rerouting existing and/or installing new utility lines, and new heating/boiler systems to provide service to these buildings. A Site Plan showing the exiting features/utilities to remain for Option B is provided as drawing S-4 in Appendix A.

The total project cost for Option B is estimated to be \$4,380,000.00, an itemized breakdown of the opinion of probable cost estimate is provided in Appendix B.

Required Permits:

- Vermont Department of Environmental Conservation Act 250 (Average processing time: 60 to 80 days).
- Construction Stormwater Discharge Permit Vermont's Construction General Permit (CGP) (Average processing time: 40 to 60 days)
- Notification to the Underground Storage Tank Program for removal of underground storage tanks.
- Local and/or State Approvals and Building/Demolition Permits.

OPTION C

Option C includes removal and disposal of all perimeter and interior fence posts, fabric, foundations, and gates; 3-foot-wide strip of asphalt under the perimeter fence; and restoring the site/disturbed areas with vegetation. A Site Demolition Plan for Option C is provided as drawing S-5 in Appendix A.

The total project cost for Option C is estimated to be \$339,000.00, an itemized breakdown of the opinion of probable cost estimate is provided in Appendix B.

Required Permits:

- Vermont Department of Environmental Conservation Act 250 (Average processing time: 60 to 80 days).
- Construction Stormwater Discharge Permit Vermont's Construction General Permit (CGP) (Average processing time: 40 to 60 days) – Note, only required if soil disturbance exceeds 1-acre
- Notification to the Underground Storage Tank Program for removal of underground

storage tanks.

• Local and/or State Approvals and Building/Demolition Permits.

OPTION D

Option D includes removal and disposal of all razor ribbon from the perimeter fence. A Site Demolition Plan for Option D is provided as drawing S-6 in Appendix A.

The total project cost for Option D is estimated to be \$187,000.00, an itemized breakdown of the opinion of probable cost estimate is provided in Appendix B.

Permitting Requirements:

No permits required.

PROJECT SCOPE ASSUMPTIONS AND EXCLUSIONS

The conceptual master plan was not developed for any particular use or construction on the property and was limited to identifying buildings, utilities, and infrastructure to be demolished or retained for each of the four (4) Options.

Identification or testing of hazardous materials was not included within this project scope, however, the estimates provide a square foot cost for hazardous material abatement/removal for each building based on the building construction type and age.

Identification or testing for soil contamination was not included within this project scope, the cost estimates for the removal and disposal of the on-site fuel storage tanks assumes there have been no past spills, leaks, or soil contamination.

Identification of permitting related to hazardous materials or contaminated soils abatement/removal was not included within this project scope.

Very truly yours,

MCFARLAND-JOHNSON, INC.

Timothy O. Bailey

Timothy D. Bailey. P.E.

Senior Project Manager

N:\18438.09 VT BGS-SESCF Master Plan\Contract Deliverables\SESCF Master Plan - Summary Narrative - Final.docx

APPENDIX A - DRAWINGS

STATE OF VERMONT DEPARTMENT OF BUILDINGS AND GENERAL SERVICES

BGS - RBH CONCEPTUAL MASTER PLAN & COST ESTIMATES

SOUTHEAST STATE CORRECTIONAL FACILITY 546 STATE FARM ROAD WINDSOR, VERMONT 05089

> AGENCY OF ADMINISTRATION DEPARTMENT OF BUILDINGS & GENERAL SERVICES 133 STATE STREET, FIFTH FLOOR MONTPELIER, VERMONT 05633-5801 JENNIFER M.V. FITCH, P.E., COMMISSIONER



PHILIP B. SCOTT **GOVERNOR**

APRIL 2022

SHEET INDEX

OPTION A - SITE DEMOLITION PLAN S-2 OPTION A - SITE PLAN

OPTION B - SITE DEMOLITION PLAN OPTION B - SITE PLAN

OPTION C - SITE DEMOLITION PLAN OPTION D - SITE DEMOLITION PLAN




MCFARLAND JOHNSON 426 INDUSTRIAL AVENUE **SUITE #164** WILLISTON, VT 05495 (802) 862-9381

CONSULTANTS 595 DORSET STREET SUITE #5 SOUTH BURLINGTON, VT 05403 (800) 639-7113 office@viscc.com

LOCATION MAP



STATE OF VERMONT



CONCEPTUAL SOUTHEAST REVISION

MASTER PL F STATE COF WINDSOR, V


ENG. JOB NO: LDG, NO: CALE: AS NOTE RAWN BY: PPROVED BY: BBI


G-001

CONSULTANTS


burlington@mjinc.com


VIS CONSTRUCTION
















SESCF Conceptual Master Plan & Cost Estimates - Option A Project: 29-Apr-22 Date:

Windsor VT

26 acre facility (Assume 10.0 Acres of disturbance)
Buildings, Site, and Utility Demolition 440,560 Description: S/F:

	Description	Qty	Unit	Cost	Total	Division Subtotals
General Sitewor		,				
Sitework	Base Site Work					
	Equipment Mobilization Filed Office Mobilization Erosion & Sediment Control Loam (2") and Seed cover	1 1 1 305,000	LS LS LS SF	\$2,500.00 \$500.00 \$15,000.00 \$0.25	\$2,500.00 \$500.00 \$15,000.00 \$76,250.00	
Demolition		eral Sitework	\$94,250			
Site Demolition	Site & Building Demolition					
Cité Demonach	Demo all above ground structures Hazardous Material Abatement Estimate	111,750 111,750	SF SF	\$20.00 \$2.00	\$2,235,000.00 \$223,500.00	
	Demo Fencing: gates razor wire 3 rows total	6 14,100	EA LF	\$1,800.00 \$12.00	\$10,800.00 \$169,200.00	
	exterior fence interior fence 3' pavement directly under fence line	3,900 1,100 11,700	LF LF SF	\$5.50 \$4.00 \$5.00	\$21,450.00 \$4,400.00 \$58,500.00	
	above grade utilities Power feed from first pole Switch Gear at tool shop Power pole removal Transformer removal Demo site lighting	3,000 1 4 21 17	LF EA EA EA	\$4.00 \$3,000.00 \$300.00 \$150.00 \$500.00	\$12,000.00 \$3,000.00 \$1,200.00 \$3,150.00 \$8,500.00	
	Pavement removal Concrete Slab and Foundation Removal Concrete slab under Sally port fence Demo water lines cut and cap hydrants	29,250 84,550 1 4	SF SF LS EA	\$5.00 \$15.00 \$35,000.00 \$500.00	\$146,250.00 \$1,268,250.00 \$35,000.00 \$2,000.00	
	Evacuate and remove Propane Tanks Evacuate and remove A.G. Fuel Tanks Evacuate and remove U.G. Fuel Tanks	1 5 3	EA EA EA	\$5,000.00 \$5,000.00 \$30,000.00	\$5,000.00 \$25,000.00 \$90,000.00	
	Demo Active Water system supply/holding and pump	1	LS	\$55,000.00	\$55,000.00	
	Demo Defunct Water System	1	LS	\$15,000.00	\$15,000.00	
	Demo all Underground Utilities except primary electric, sanitary sewer, and storm sewer to remain.	1	LS	\$360,000.00	\$360,000.00	
	· T			•	subTotal	\$4,752,200
	Subtotal				4,846,450	\$4,846,450
	General Conditions					\$154,878
	Permitting	0.50%				\$24,232
	Contingency	5%				\$251,278
	Overhead & Profit	2.5%				\$131,921
	Project Subtotal					\$5,408,759
	P & P Bond	1%				\$54,088
PROJECT TOTAL						\$5,462,847
	I/f = Linear Foot, S/F = Square Foot, cy = Cubi	c Yard, cf = Cul	oic Foot, ea. =	Each, Allow = Allow	vance, ls = Lump Sum, gal	= Gallons

1 of 1 4/29/2022

SESCF Conceptual Master Plan & Cost Estimates - Option B Project: 29-Apr-22 Date:

Windsor VT
Description: 26 acre facility (Assume 8.0 Acres of disturbance)
Buildings, Site, and Utility Demolition S/F: 360,000

	Description	Qty	Unit	Cost	Total	Division Subtotals
General Si		·				
Sitework	Base Site Work					
	Equipment Mobilization	1	LS	\$2,500.00	\$2,500.00	
	Filed Office Mobilization Erosion & Sediment Control	1	LS LS	\$500.00 \$15,000.00	\$500.00 \$15,000.00	
	Loam (2") and Seed cover	195,000	SF	\$0.25	\$48,750.00	
						\$66,750
				subTota.	,	·
Demolition				SubTotal	,	\$66,750
	Site & Building Demolition					
	Demo all above ground structures	89,650	SF	\$20.00	\$1,793,000.00	
	Hazardous Material Abatement Estimate	89,650	SF	\$2.00	\$179,300.00	
	Demo Fencing:					
	gates razor wire 3 rows total	6 14,100	EA LF	\$1,800.00 \$12.00	\$10,800.00 \$169,200.00	
	exterior fence	3,900	LF	\$5.50	\$21,450.00	
	interior fence 3' wide pavement under perimeter fence	1,100 11,700	LF SF	\$4.00 \$5.00	\$4,400.00 \$58,500.00	
		, , , , ,	<u> </u>	V 0.00	400,000.00	
	above grade utilities Power feed from first pole	3,000	LF	\$4.00	\$12,000.00	
	Switch Gear at tool shop Power pole removal	1 9	EA EA	\$3,000.00 \$300.00	\$3,000.00 \$2,700.00	
	Transformer removal	21	EA	\$150.00	\$3,150.00	
	Demo site lighting	5	EA	\$350.00	\$1,750.00	
	Pavement removal	18,320	SF	\$5.00	\$91,600.00	
	Concrete Slab and Foundation Removal Concrete slab under Sally port fence	63,150 1	SF LS	\$15.00 \$35,000.00	\$947,250.00 \$35,000.00	
	demo water lines cut and cap hydrants	1	ĒĀ	\$500.00	\$500.00	
	Evacuate and remove Propane Tanks	1	EA	\$5,000.00	\$5,000.00	
	Evacuate and remove A.G. Fuel Tanks Evacuate and remove U.G. Fuel Tanks	5 3	EA EA	\$5,000.00 \$30,000.00	\$25,000.00 \$90,000.00	
				·	·	
	Demo Defunct Water System Demo All Underground Utilities except	1	LS	\$5,000.00	\$5,000.00	
	what's needed for useable buildings.	1	LS	\$260,000.00	\$260,000.00	
				subTotal		\$3,718,600
Utilties						
ı	Add Heating Systems	3	Each	\$25,000.00	\$75,000.00	
	Convert heating system to propane	I	Each	\$10,000.00	\$10,000.00	
	Subtotal			1	3,870,350	\$85,000 \$3,870,350
	General Conditions				-,,	\$154,878
		1%				
	Permitting	Incl				\$3,870 \$0.00
	Insurance	5%				\$0.00 \$201,455
	Contingency					
	Overhead & Profit	2.5%				\$105,764
	Project Subtotal	40.				\$4,336,317
	P & P Bond	1%				\$43,363
	OTAL W/ BOND					\$4,379,680
I/f =	Linear Foot, S/F = Square Foot, cy = Cubic Ya	ard, ct = Cubic	⊢oot, ea.	= Lach, Allow = Allowance	, Is = Lump Sum, ga	aı = Gallons

Project: 28-Apr-22 SESCF Conceptual Master Plan & Cost Estimates - Option C Date:

Windsor VT 26 acre facility (5,000 LF of Fencing & 14,100 LF of Razor Ribbon) Fence and Site Demolition L/F: 19,100 Description:

	Description	Qty	Unit	Cost	Total	Division Subtotals
General Sitewor	rk					
Sitework	Base Site Work	T				
	Equipment Mobilization Filed Office Mobilization Erosion & Sediment Control	1 1 1	LS LS LS	\$1,000.00 \$500.00 \$5,000.00	\$1,000.00 \$500.00 \$5,000.00	
	Loam (2") and Seed cover	11,700	SF	\$0.25	\$2,925.00	
						\$9,42
					subTotal	\$9,42
Demolition						
Site Demolition	Site Demolition					
	Demo Fencing:					
	gates razor wire 3 rows total	14 100	EA LF	\$1,800.00 \$12.00	\$10,800.00	
	exterior fence	14,100 3,900	LF LF	\$12.00 \$5.50	\$169,200.00 \$21,450.00	
	interior fence	1,100	LF	\$4.00	\$4,400.00	
	3' pavement directly under fence line	11,700	SF	\$5.00	\$58,500.00	
	Concrete slab under Sally port fence	1	LS	\$35,000.00	\$35,000.00	
						\$299,35
					subTotal	\$299,35
		Ι			002.010	\$250,00
	Subtotal				308,775	\$308,775
	General Conditions	1%				\$3,088
	Permitting	1%				\$3,088
	Contingency	5%				\$15,748
	Overhead & Profit	2.5%				\$8,267
	Project Subtotal				Ī	\$338,965
ROJECT TOTAL	•			<u>_</u>		\$338,965

Project: 28-Apr-22 SESCF Conceptual Master Plan & Cost Estimates - Option D Date:

Windsor VT

26 acre facility (14,100 LF of Razor Ribbon)
Razor Ribbon Demolition Description: 14,100 L/F:

	Description	Qty	Unit	Cost	Total	Division Subtotals
General Sitework	k					
Sitework	Base Site Work					
	Equipment Mobilization Filed Office Mobilization	1 1	LS LS	\$2,500.00 \$500.00	\$2,500.00 \$500.00	
		I		•		\$3,00
Demolition						
Site Demolition	Site Demolition					
	Demo Fencing: razor ribbon 3 rows total	14,100	LF	\$12.00	\$169,200.00	\$169,20
				<u> </u>	subTotal	\$169,2
	T					
	Subtotal				172,200	\$172,20
	General Conditions	1%				\$1,72
	Contingency	5%				\$8,69
	Overhead & Profit	2.5%				\$4,56
	Project Subtotal					\$187,18
ROJECT TOTAL	W/ BOND					\$187,18